BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT1351

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/13/2023-24, Date: 26-12-2023

Name of Work: Removal of silt & Repair and maintenance of footpath in new ward no. 12 Doddabommasandra.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRAKASH NAIK H	
				In Figures	In Words
1	439.50	Removing and resetting of footpath slab	Sqm	241.82	Rupees Two Hundred Forty One and Eighty One Paise Only
2	288.00	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc., complete	hr	1389.15	Rupees One Thousand Three Hundred Eighty Nine and Fifteen Paise Only
3	1440.00	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc., complete	hr	1452.95	Rupees One Thousand Four Hundred Fifty Two and Ninety Four Paise Only
4	234.00	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drain age of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	1324.32	Rupees One Thousand Three Hundred Twenty Four and Thirty Two Paise Only
5	10.80	Supplying and fixing Pre cast reinforced concrete slab 23cm thick including cost of reinforcement as per design and drawing courses cost of all materials, labour complete as per specifications.	Sqm	5183.07	Rupees Five Thousand One Hundred Eighty Three and Seven Paise Only
6	27.00	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregate	Cum	7066.45	Rupees Seven Thousand Sixty Six and Forty Five Paise Only
7	1.00	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works.	t	44452.80	Rupees Forty Four Thousand Four Hundred Fifty Two and Eighty Paise Only
8	291.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2896.53	Rupees Two Thousand Eight Hundred Ninety Six and Fifty Three Paise Only
9	1728.00	Supply of Unskilled Mazdoor Heavy Labours As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	662.06	Rupees Six Hundred Sixty Two and Five Paise Only
10	288.00	Supply of Skilled Mason or Brick layer Class-1 As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	696.29	Rupees Six Hundred Ninety Six and Twenty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike